

SRS Degadur R17LM Specification

PART 1 – GENERAL

1.1 WORK INCLUDED

- A. Work described in this section includes surface preparation and installation of R17LM Methyl Methacrylate (MMA) Acrylic Polymer Concrete Systems.
- B. See drawings for locations and quantities.

1.2 RELATED WORK - Specified elsewhere

- A. Cast-in-place concrete (Section 03300)
 - 1. See Paragraph 1.08 - Requirements for New Concrete.
- B. Painting (Section 09900)

1.3 SYSTEM DESCRIPTION

- A. The overlay/patching mortar shall be a two-component system based on solvent-free, 100% reactive Methyl Methacrylate (MMA) Acrylic liquid and a powder component composed primarily of sand, polymers, and other inert fillers along with a curing agent.
- B. The polymer concrete cures to full mechanical strengths, full chemical resistances, and are available to normal traffic in no more than 90 minutes at 68°F. The cured material has a minimum compressive strength of 7,800 psi in accordance with ASTM C39. Cured overlays have an abrasion resistance at least twice that of standard 3,000 psi concrete in accordance with ASTM C501.
- C. The finished floor coating/patching system shall be uniform in color, texture, and appearance. All edges that terminate at walls, floor discontinuities, and other embedded items shall be sharp, uniform, and cosmetically acceptable with no thick or ragged edge. The Contractor shall work out an acceptable masking technique to ensure the acceptable finish of all edges.

1.4 QUALITY ASSURANCE

- A. Manufacturer Qualifications:
 - 1. Acceptable manufacturer: BASF Building Systems/SRS 889 Valley Park Drive, Shakopee, MN 55375 Phone: 800-433-9517. Distributed by Righter Group, Inc. 11 Upton Drive, Wilmington, MA 01887 (800) 533-3003, <http://www.rightergroup.com>
 - 2. No request for substitution shall be considered that would change the generic type of coating system specified (i.e., 100% reactive, Methyl Methacrylate based acrylic liquid). Equivalent materials of other manufacturer's may be substituted only on approval of the Architect or Engineer. Requests for substitution will be considered if submitted within 10 days after the execution of the contract. Requests shall include the respective manufacturer's technical literature for each product giving the name, generic type, descriptive information, recommended dry film thickness (DFT), Material Safety Data Sheet (MSDS), and certified test reports showing results to equal performance criteria of products specified herein.

3. Manufacturer must show a minimum of a 10 year history of manufacturing MMA Polymer Concrete for the stadium industry. Manufacturer must show a minimum of 10 projects of equal size and magnitude of this project.

B. Applicator Qualifications:

1. Pre-qualification requirements: Each bidder for this project shall be prequalified and approved by the material manufacturer at the time of bid submittal. Acceptability will include judgment on equipment, history, and financial strength. In no case will BASF/SRS permit the application of any of its materials by untrained, non-approved Contractor or personnel.
2. Each approved applicator shall have been trained by the Manufacturer in all phases of surface preparation and application of the specified flooring system(s).
3. Each approved applicator must have five years experience of installing the specified flooring system and submit a list of five projects/references as a prequalification requirement. All of the five projects/references must be of the same type, equal size, quantity, and magnitude to this project as a prequalification requirement. Owner has the option to personally inspect the projects/references to accept or reject any of the Contractors prior to bid time as a prequalification requirement.

C. Subcontractor Qualifications:

1. The only approved and specified subcontractors for this resurfacing work shall be for shot-blast cleaning of the concrete substrate.

D. Acceptance Sample:

1. A minimum one-foot square representative sample of the specified flooring system shall be prepared by the Manufacturer's representative and submitted to the Owner prior to the bidding phase of the project. All bidders shall inspect the "acceptance sample" before submitting their bids.
2. The installed flooring system shall be similar to the acceptance sample in thicknesses of respective film layers, color, texture, overall appearance and finish.

E. Bond Testing:

1. Surface preparation efforts shall be evaluated by conducting Bond Tests at the site prior to application of the flooring system(s).
2. See paragraph 3.03 - B or consult with Material Manufacturer for specific procedure.

F. Pre-Job Meeting

1. Owner requires a Pre-Job Meeting with representatives of Owner, Contractor/Applicator, and Material Manufacturer in attendance. The agenda shall include a review and clarification of this specification, application procedures, quality control, inspection and acceptance criteria, and production schedules. Applicator is not authorized to proceed until this meeting is held or waived by Owner.

1.5 REFERENCE STANDARDS

- A. ACI 308 - Standard Practice for Curing Concrete
- B. ACI 302.1R-80 - Guide for Concrete Floor and Slab Construction

- C. United States Department of Agriculture (USDA) and Food and Drug Administration (FDA) authorization for incidental contact with foodstuffs.

1.6 SUBMITTALS

- A. Acceptance Sample: One-foot square (1 ft. by 1 ft.) sample of the specified acrylic flooring system applied to hardboard or similar backing for rigidity and ease of handling.
- B. Manufacturer's Literature: Descriptive data and specific recommendations for surface preparation, mixing, and application of materials.
- C. Manufacturer's Material Safety Data Sheets (MSDS) for each respective product to be used.

1.7 DELIVERY, STORAGE, AND HANDLING

- A. All material shall be delivered in original Manufacturer's sealed containers with all pertinent labels intact and legible.
- B. Store materials in dry protected area between 25° and 80° Fahrenheit. Keep out of direct sunlight. Protect from open flame; keep all containers grounded.
- C. Follow all Manufacturer's specific label instructions and prudent safety practices for storage and handling.

1.8 PROJECT/SITE CONDITIONS

- A. Material, air, and surface temperatures shall be in the range of 25° to 85° Fahrenheit during application and cure, unless a special formulation is being used and Manufacturer has been consulted.
- B. Relative humidity in the specific location of the application shall be less than 85 percent and the surface temperature shall be at least 5 degs. above the dew point.
- C. Conditions required of new concrete to be coated with MMA materials:
 - 1. Concrete shall be moisture cured for a minimum of 7 days at 70° F. The concrete must be fully cured for a minimum of 28 days prior to application of the coating system pending moisture testing.
 - 2. Surface contaminants such as curing agents, membranes, or other bond breakers should not be used.
 - 3. Concrete shall have a "steel trowel" finish concrete (a "burnished" finish is neither necessary nor desirable).
 - 4. Drains should be set to the concrete grade rather than raised to the finished grade of the topping.
- D. Foodstuffs are the responsibility of the Owner and shall have been removed from the area of application by the Owner or his representatives.
- E. Vapor barriers and/or suitable means shall have been installed beneath grade slabs to prevent vapor transmission.

1.9 WARRANTY

- A. BASF Building Systems (BBS) warrants that materials shipped to buyers are at the time of shipment substantially free from material defects and will perform substantially according to SRS's published literature if used strictly in accordance with SRS's prescribed procedures and prior to expiration date.

- B. BBS liability with respect to this warranty is strictly limited to the value of the material purchased.
- C. BBS has no responsibility for the application and processing of products and is under no circumstances liable to any third party whatsoever.

1.10 SEQUENCING/SCHEDULING

PART 2 – PRODUCTS

2.1 ACCEPTABLE MANUFACTURERS

- A. BASF Building Systems 889 Valley Park Drive, Shakopee, MN 55375 Phone: 800-433-9517. Distributed by Righter Group, Inc. 11 Upton Drive, Wilmington, MA 01887 (800) 533-3003, <http://www.rightergroup.com>

2.2 MATERIALS

A. R17LM Polymer Concrete:

1. Saturating Primer/Sealer Coat:
Degadur R41 Low Viscosity Primer with i-Component
2. Mortar: Degadur R17LM Polymer Concrete

2.3 PRODUCT PERFORMANCE CRITERIA

A. Degadur R41i Low Viscosity Primer

- | | |
|---|---------|
| 1. Percentage Reactive Resin: | 100% |
| Percentage Solids: | 100% |
| 2. Water Absorption, % Wt.(ASTM D570): | < 0.6% |
| 3. Tensile Strength, psi (ASTM D638): | 3550 |
| 4. Tensile Modulus, psi X 10 ⁵ (ASTM D638): | 2.1 |
| 5. Coefficient of Thermal Expansion, (ASTM D696) in./in./deg. F | .000035 |
| 6. Electrical Resistivity (ASTM D257): | |
| Volume Resistance, ohm-cm: | 1015 |
| Surface Resistance, ohm: | 1012 |
| 7. Water Vapor Transmission (DIN 53122), g/cm-hr-mm Hg X 10 ⁻⁹ : | 1.4 |

B. Degadur R17LM High Strength Polymer Concrete Mortar

- | | |
|---|--------|
| 1. Percentage Reactive Resin | 100% |
| Percentage Solids: | 100% |
| 2. Water Absorption, % Wt. (ASTM D570): | < .02% |
| 3. Abrasion Resistance (ASTM C501) grams lost per 1000 cycles: | 3.5 |
| 4. Compressive Strength, psi (ASTM C39): | 7,800 |
| 5. Compressive Modulus, psi X 10 ⁶ (ASTM C469): | 1.2 |
| 6. Tensile Strength, psi (ASTM D638): | 1,200 |
| 7. Flexural Strength, psi (ASTM D790): | 2,800 |
| 8. Coefficient of Thermal Expansion (ASTM C531) in./in./deg.F. X 10 ⁻⁷ : | 1.8 |
| 9. Electrical Resistivity, (ASTM D257) Volume Resistivity, ohm-cm: | 1013 |

10. Chemical Resistance, ASTM D543:	
Effect of alkalis:	none
Effect of salt solutions:	none
Effect of, oil, grease:	none
Effect of sunlight (UV radiation):	none

2.4 PRODUCT INSTALLATION & APPLICATION CRITERIA

A. All SRS Degadur Material Systems:

1. Pot Life at 68° F.: 10-15 minutes
2. Cure Time at 68° F.: 60 minutes
3. Recoat Time at 68° F.: 60-90 minutes

2.5 MIXES

- ### A. Follow Manufacturer's prescribed procedures and recommendations.

PART 3 – EXECUTION

3.1 PREWORK INSPECTION

- A. Examine all surfaces to be coated with MMA material systems and report to the Owner and/or Engineer any conditions that will adversely affect the appearance or performance of these coating systems and that cannot be put into acceptable condition by the preparatory work specified in Paragraph 3.03.
- B. Do not proceed with application until the surface is acceptable or authorization to proceed is given by the Engineer.
- C. In the event that Applicator has employed all acceptable methods of surface preparation and cannot remedy adverse conditions that would lead to failure of the installation, Applicator shall withdraw from the contract and Owner will be financially responsible only for preparation efforts.

3.2 GENERAL

- A. Material storage area must be selected and approved by Applicator and Owner or his representative.
- B. Owner will furnish ____ V ____ Phase electricity and water for use by Applicator.
- C. If existing ventilation is inadequate, Applicator will provide sufficient ventilation to allow complete air exchange every five (5) minutes.
- D. Owner shall provide means for disposal of construction waste.
- E. Applicator will protect adjacent surfaces not to be coated with masking and/or covers. Owner's equipment shall be protected from dust, cleaning solutions, and flooring materials.

3.3 PREPARATION

- #### A. Surface Preparation - General

1. Concrete substrate must be clean and dry. Dislodge dirt, mortar spatter, paint overspray, and other dry surface accumulations and contamination by scraping, brushing, sweeping, vacuuming, and/or compressed air blow down.
2. New concrete: See 1.08 - C for requirements.
3. Surfaces that are heavily contaminated shall be cleaned with the appropriate degreaser, detergent, or other appropriate cleaner/surfactant followed by thoroughly rinsing with fresh water to remove the accumulation prior to mechanical cleaning efforts. Mechanical cleaning will not remove such deposits, but only drive them deeper.

B. Bond Testing

1. The applicator shall evaluate all surface preparation by conducting bond tests at strategic locations.
2. Mix six (6) ounces of the primer to be used in the application with #10-#12 mesh, dry quartz sand until an easily trowelable mixture is obtained. Add 10% by volume SRS Powder Hardener and mix well. Apply palm-sized patties 1/8" to 1/4" thick.
3. After one (1) hour at (68° F.), patties must be cured tack-free and cooled to ambient temperature of concrete. Remove patties with hammer and chisel and examine fracture/delamination plane. Concrete with fractured aggregate must be attached to the entire underside of the patty.
4. If only laitance or a small amount of concrete is attached or if interface between patty and substrate is tacky, further substrate preparation is required.
5. If further surface preparation is required, bond tests shall be conducted again when this has been completed.
6. If no amount or kind of surface preparation produces satisfactory bond tests, the applicator shall report that to the Owner, Engineer, and Manufacturer.

C. Mechanical Surface Preparation and Cleaning

1. All accessible concrete floor surfaces shall be mechanically blast cleaned using a mobile steelshot, dust-recycling machine such as BLASTRAC, as manufactured by Wheelabrator Corp., or approved equivalent. All surface and embedded accumulations of paint, toppings, hardened concrete layers, laitance, power trowel finishes, and other similar surface characteristics shall be completely removed leaving a bare concrete surface having a profile similar to 40 grit sandpaper and exposing the upper fascia of concrete aggregate.
2. Floor areas inaccessible to the mobile blast cleaning machines shall be mechanically abraded to the same degree of cleanliness, soundness, and profile using vertical disc scarifiers, starwheel scarifiers, needle guns, scabblers, or other suitably effective equipment.
3. After blasting, traces or accumulations of spent abrasive, laitance, removed toppings, and other debris shall be removed with brush or vacuum.
4. Conduct Bond Tests to check adequacy of surface preparation. See Paragraph 3.03 - B (Bond Testing).
5. Application of the respective specified material system(s) must be completed before any water or other contamination of the surface occurs.

3.4 INSTALLATION – General

A. Application of Degadur R17 Polymer Concrete consists of:

1. Applying the primer, Degadur R41i.
2. Applying the Degadur R17 Mortar.

- B. Time for curing (60-90 minutes) shall be allowed between each coat.
- C. Thicknesses are specified below and/or in Paragraph 3.07.
- D. Open only the containers of component materials to be used in each specific application as needed. Refer to Manufacturer's data sheets for pot-life/temperature relationship to determine size of batches to mix and mix ratios for each respective coat of the system.
- E. Pot life is short, so mix only as much material at a time as can be easily and efficiently applied.

3.5 PRIME COAT

- A. Pour the mixed batches onto the floor surface and use a 18" wide, 1/2" - 3/4" thick-napped, solvent-resistant paint roller to roll out the material at a rate of 100 sq. ft./ gal. to form a uniform, continuous film, ensuring that all crevices, cracks, and other surface discontinuities have been saturated and coated. Use a paint brush to reach areas inaccessible to the roller. Work quickly and deliberately; the pot life is short (10-15 minutes). Do not leave any "puddles"; roll out any such accumulations.
- B. Allow the primer/sealer coat to cure.

3.6 PATCHING

- A. Holes deeper than 1/4" shall be patched and filled with R17 mortar. Surface preparation and priming of these holes is necessary; see 3.03 and 3.04.01.
- B. Deep Patching: If there are large differences in the depth of the hole (e.g., if one side is 6" deep and the other is 2" deep), filling should be done in a two (2) step operation. Fill the deeper side up to the level of the shallower side. Let the polymer concrete cure and cool. Then reprime, let primer cure, and fill remainder of hole.
- C. For very deep patching, the R17 Mortar may be extended. Follow Manufacturer's prescribed recommendations for mix ratios and installation procedures.

3.7 TOPPING (OVERLAYS)

- A. Mix a maximum of 54 oz. of liquid component with a 31 lb. bag of powder component. The quantity of liquid component may be reduced to obtain desired mortar consistency, but the mix shall not be less than 50 or greater than 64 fluid ounces to one 31 lb. bag of powder component. Too little liquid creates a stiff mix that may not properly bond to the primer; too much liquid can result in shrinkage cracks.
- B. When using bag-mixing method, pour the entire bag at once and spread the topping material with a gauge rake (available from the manufacturer) set to a minimum depth of 1/4". Trowel down lightly to a uniform thickness or employ the use of a screed system for application.
- C. (If Required) Immediately back roll using porcupine roller to create a slip resistant texture.

3.8 FIELD QUALITY CONTROL/INSPECTION

- A. Applicator shall request acceptance of surface preparation from the Engineer before application of the prime/seal coat.
- B. Applicator shall request acceptance of the prime/seal coat from the Engineer before application of subsequent specified materials.
- C. All work not acceptable to the Architect, Engineer, or Owner must be corrected before consideration of final acceptance.

3.9 CLEANING

- A. Applicator shall remove any material spatters and other material that is not where it should be. Remove masking and covers taking care not to contaminate surrounding area.
- B. Applicator shall repair any damage that should arise from either the application or clean-up effort.

Specifier Note: This product guide specification is written according to the Construction Specifications Institute (CSI) Format, including *Master Format*, *Section Format*, and *Page Format*, contained in the *CSI Manual of Practice*.

The section must be carefully reviewed and edited by the Architect to meet the requirements of the project and local building code. Coordinate this section with other specification sections and the drawings.

Delete all "Specifier Notes" when editing this section.

Specifier Notes: This section covers Degadur high-performance coating systems for commercial facilities.

This specification is only a guide listing various coating system options for various environments and should not be used as a final specification. Additional coating systems not listed in this specification are available, and may be more appropriate for your coating application. To finalize this specification, please contact www.rightergroup.com

Most coatings specified contain organic solvents. Consult Righter Group for compliance to local VOC regulations.

Righter Group, Incorporated
11 Upton Drive
Wilmington, MA 01887
Phone: (800) 533-3003 Fax: (800) 988-9824

July 2007